

STERIS CORPORATION

ACUHOLD

DES. **R. LA BRIE**

JOB NO. **14-0905**

DATE **6/10/09**


SHEET

1

OF **1** SHEETS

SEISMIC ANCHORAGE

WALL MOUNTED



PLAN AT WALL

SIDE ELEVATION

LOADS: PER 2007 CALIFORNIA BUILDING CODE SECTION 1613A AND ASCE 7-05 SECTIONS 12 AND 13.

(ALLOWABLE STRESS DESIGN IS USED)

WEIGHT = 100 LBS.

HORIZONTAL FORCE (E_h) = $0.97W_p$ = 97 LBS.

VERTICAL FORCE (E_v) = $0.27W_p$ = 27 LBS.

1/4" TEK SCREWS TO 16 GAGE, 50 KSI

$T_{ALLOW.}$ = 260 LBS

$V_{ALLOW.}$ = 612 LBS

TENSION (T)

$$T_{VERTICAL} = \frac{(100\# + 27\#)7.6''}{3_{SCREWS}(4'')} = 80 \text{ LBS}$$

$$T_{PARALLEL} = \frac{97\#(7.6'')(8'')}{32''(4'')} = 46 \text{ LBS}$$

$$T_{PERP.} = \frac{97\#(6.2'')}{3_{SCREWS}(4'')} = 50 \text{ LBS}$$

$$T_{MAX} = 80\# + \sqrt{46^2 + 50^2} = 148 \text{ LBS/SCREW (MAX)}$$

SHEAR (V)

$$V_{MAX} = \frac{100\# + 27\#}{3_{SCREWS}} + \frac{97\#(6.2'')}{3_{SCREWS}(4'')} = 92 \text{ LBS/SCREW (MAX)}$$

