

Appendix 1F. EQUIPMENT RESPONSIBILITY

1. DEFINITIONS

1.1 In this Schedule:

- (a) "Acceptance Protocol" has the meaning set out in Section 6.10 of this Schedule;
- (b) "Category 1 Equipment" means the equipment described and listed as "Category 1" in the Equipment Lists (or similar equipment);
- (c) "Category 2 Equipment" means the equipment described and listed as "Category 2" in the Equipment Lists (or similar equipment);
- (d) "Category 3 Equipment" means the equipment described and listed as "Category 3" in the Equipment Lists (or similar equipment);
- (e) "Category 4 Equipment" means the equipment described and listed as "Category 4" in the Equipment Lists (or similar equipment);
- (f) "Commission" means to test and commission the equipment or system in accordance with any commissioning requirements set out in this Agreement, and applicable standards and good industry practice, including to ensure that the Equipment is operating in accordance with the manufacturer's requirements and specifications, and "Commissioned" and "Commissioning" have a corresponding meaning;
- (g) "Deliver" means to deliver Equipment to the Facility, and "Delivered" and "Delivery" have corresponding meanings;
- (h) "Equipment" means the Category 1 Equipment, the Category 2 Equipment, the Category 3 Equipment and the Category 4 Equipment as described in Appendix 1F Herein.
- (i) "Equipment Committee" means the committee established pursuant to Section 6.7 of this Schedule;
- (j) "Equipment Data Sheets" means the equipment data sheets set out in the Equipment List containing specifications for items of equipment on the Equipment List, as those data sheets may be updated in accordance with this Agreement;
- (k) "Equipment Lists" means Appendix 1F: EQUIPMENT, Herein.
- (l) "Equipment Logistics Schedule" has the meaning set out in Section 6.11 of this Schedule;
- (m) "Install" means to install in the Facility, including making connections to necessary building services (including plumbing, heating, cooling, ventilation and electricity) and connections to necessary communication or network interfaces or devices, and "Installed" and "Installation" have corresponding meanings;
- (n) "Receive" means the provision of equipment and staff to accept Delivery and provide an appropriate and secure staging and storage area to be used prior to Setup, and "Received" and "Receiving" have corresponding meanings;
- (o) "Setup" includes:

- (i) transportation and movement within the Facility from the Delivery or storage location to the final installation location;
 - (ii) placement in the final location within the Facility; and
 - (iii) any necessary unwrapping, unpacking, disposing and/or recycling all wrapping and packaging materials, assembly.
- (p) "Supply" means the management and completion of procurement processes, up to and including Delivery, for Equipment, including the payment to vendors, and "Supplied" has a corresponding meaning.

2. CATEGORY 1 EQUIPMENT (DESIGN-BUILDER SUPPLIED, DESIGN-BUILDER INSTALLED)

2.1 Responsibilities for Category 1 Equipment

The Design-Builder will Supply, Deliver, Receive, Setup, Install and Commission all Category 1 Equipment.

2.2 Standards for Equipment

The Design-Builder will cause all Category 1 Equipment to be:

- (a) new;
- (b) of good quality and in a safe, serviceable and clean condition in accordance with the Equipment List;
- (c) of the type specified in the Statement of Requirements, if applicable;
- (d) in compliance with all Laws; and
- (e) in compliance with all certifications or standards that would be reasonable for similar equipment in a similar application if Supplied and Installed by the Authority.

The Design-Builder will, as soon as practicable after receiving a request from the Authority, supply to the Authority evidence demonstrating its compliance with this Section **Error! Reference source not found..**

2.3 Warranties

The Design-Builder will ensure that all manufacturer's and vendor's warranties for all Category 1 Equipment:

- (a) commence no earlier than the date of first clinical use of the relevant item of Category 1 Equipment; and
- (b) are in the Authority's name.

2.4 Training

The Design-Builder will include the Authority staff and other representatives to be notified and included in all stages of the Receiving, Setup, Installation and Commissioning to ensure there is a comprehensive overview of the Equipment, including its features, calibration and interfaces.

The Design-Builder will be knowledgeable on the proper use and maintenance of all Category 1 Equipment and will provide sufficient training and education of the Authority and persons designated by the Authority to enable proper use and maintenance of the Category 1 Equipment. The Design-Builder will not be responsible for providing the Authority with training and education in respect of Category 3 Equipment, Category 2 Equipment and Category 4 Equipment.

On or before the Target Building Substantial Completion Date, the Design-Builder will transfer and deliver to the Authority all guidance material and manuals relating to Category 1 Equipment items as produced and provided by the manufacturer or the vendor of such items.

3. CATEGORY 2 EQUIPMENT (AUTHORITY SUPPLIED, DESIGN-BUILDER INSTALLED)

3.1 Responsibilities For Category 2 Equipment

The Authority intends to, but is not obligated to, Supply the Category 2 Equipment.

The Design-Builder will Receive, Setup, Install and Commission all Category 2 Equipment.

The Design-Builder will be responsible for notifying the Authority of any Category 2 Equipment that is Delivered damaged or short of the complete quantities on the weigh bill/bill of lading. Such discrepancy will be noted on the weigh bill/bill of lading provided to the shipper.

3.2 Timing of Delivery and Installation of Category 2 Equipment

The Design-Builder will:

- (a) as early as practicable provide on the Equipment Logistics Schedule the dates by which each item of Category 2 Equipment must be Delivered, Installed and Commissioned so as not to delay the Design, the Construction, Substantial Completion of the Building or the Authority's use and occupation of the Facility; and
- (b) as required from time to time until Substantial Completion of the Building, but no less than once per calendar month, update the information in Section 3.2(a) above so that at all times it is an accurate, reasonable and realistic representation of the Design-Builder's plans for the completion of the Design and Construction of the Facility.

The Authority will cause each item of Category 2 Equipment to be Delivered by the date specified by the Design-Builder under Section 3.2(a) above.

4. CATEGORY 3 EQUIPMENT (AUTHORITY SUPPLIED, AUTHORITY INSTALLED)

4.1 Responsibilities For Category 3 Equipment

The Authority intends to, but is not obligated to, Supply, Receive, Setup, Install and Commission the Category 3 Equipment.

4.2 Timing of Delivery and Installation of Category 3 Equipment

The Design-Builder will:

- (a) as early as practicable:

- (i) for each item of Category 3 Equipment, provide on the Equipment Logistics Schedule the earliest date when the Facility will be available to the Authority to Install such item, which date must, for all Category 3 Equipment and any required Setup or Installation equipment that will not fit through the constructed doorways and other physical constraints on access, be a reasonable period in advance of the construction of such doorways and other physical constraints on access; and
 - (ii) identify to the Authority the date by which each item of Category 3 Equipment must be Delivered, Installed and Commissioned so as not to delay the Design, the Construction, Substantial Completion of the Building or the Authority's use and occupation of the Facility; and
- (b) as required from time to time until Substantial Completion of the Building, but no less than once per calendar month, update the information in Section 4.2(a) above so that at all times it is an accurate, reasonable and realistic representation of the Design-Builder's plans for the completion of the Design and Construction of the Facility.

The Authority will cause the relevant item of Category 3 Equipment the Authority wishes to have Installed in the Facility to be Delivered by the date specified by the Design-Builder under Section 4.2(a) above.

4.3 Timing of Delivery and Installation of Category 3 Equipment

Subject to Section 4.2(a)(i) above and unless otherwise noted on the Equipment List or the Equipment Logistics Schedule, no Category 3 Equipment will be Delivered prior to Substantial Completion of the Building. Delivery after Substantial Completion of the Building will not relieve the Design-Builder of its obligations under the Design-Build Agreement to complete the Design and Construction to accommodate the Equipment in the Facility and the obligations under this Schedule.

5. CATEGORY 4 EQUIPMENT (AUTHORITY RELOCATED)

5.1 Responsibilities for Category 4 Equipment

The Authority intends to, but is not obligated to, relocate the Category 4 Equipment from its existing location to the new Facility. The Authority may, at its discretion, Supply new Category 4 Equipment in lieu of relocating existing Category 4 Equipment and may designate it for purposes of this Appendix 1F – Equipment as Category 4 Equipment or alternatively as Category 3 Equipment, Category 2 Equipment or Category 1 Equipment. A change to the Design-Builder's obligations by a re-designation as Category 2 Equipment or Category 1 Equipment will be implemented as a Change.

5.2 Timing of Delivery and Installation of Category 4 Equipment

Unless otherwise noted on the Equipment List or the Equipment Logistics Schedule, no Category 4 Equipment will be Delivered prior to Substantial Completion of the Building. Delivery after Substantial Completion of the Building will not relieve the Design-Builder of its obligations under the Design-Build Agreement to complete the Design and Construction to accommodate the Equipment in the Facility and the obligations under this Schedule.

6. GENERAL

6.1 Integration of Equipment with Design of Facility

The Design-Builder will ensure that all Equipment is integrated with the overall Design of the Facility and will include such Equipment as part of the development of Design under this Agreement. To the extent practicable, any required changes to the Design of the Facility as a result of changes to Equipment requirements will be resolved as part of the Design development process.

6.2 Changes affecting Design or Construction

If the Authority increases or decreases the quantities of Equipment, procures other items in substitution for those identified on the Equipment List or otherwise changes the items to be procured and there is an effect on the Design or Construction, such increase, decrease, procurement or change, and the effect thereof, will constitute a Change. The parties will endeavour to agree to an expedited Change process to deal with Equipment changes.

6.3 Staging and Storage

The Design-Builder will:

- (a) provide a secure, dry space to accommodate staging and storage of Equipment;
- (b) allow Authority representatives to access and work within the space;
- (c) will ensure that the space is able to maintain a reasonable temperature to store and work in; and
- (d) provide power to the space and will notify the Authority, in advance, of any power interruptions.

6.4 Storage Costs

The Authority will reimburse the Design-Builder for any incremental out of pocket storage costs for any item of Category 3 Equipment or Category 2 Equipment if such item is Delivered materially in advance of the earliest delivery date for such item as identified by the Design-Builder under Section 4.2(a) or 3.2(a) of this Schedule in the Equipment Logistics Schedule.

Any storage costs incurred by the Design-Builder due to Equipment being Delivered by the delivery date as set out in the Equipment Logistics Schedule delivery date, but not ready for Setup, will be borne by the Design-Builder.

6.5 Equipment Commissioning

The Design-Builder will incorporate its Commissioning responsibilities under this Schedule into its commissioning activities for the Facility as contemplated in this Agreement.

All Category 2 and Category 3 Equipment must be Commissioned, and the Acceptance Protocol completed where applicable, prior to Substantial Completion of the Building.

6.6 Addition of Additional Equipment or Replacement of Existing Equipment

If the Authority identifies Equipment that is in addition to, or in replacement of certain items of, the Equipment, the Authority may in its discretion:

- (a) elect to have the Design-Builder Supply, Deliver, Receive, Setup, Install and/or Commission such additional Equipment, in accordance with and subject to the procedures for Changes; or
- (b) itself perform any of such activities.

6.7 Equipment Committee

The parties will establish an Equipment Committee composed of 2 (or any other number agreed between the parties) representatives of each party. The Equipment Committee will meet regularly (and not less than once per month) to review the status of, and to provide advice to the parties with respect to the Equipment Supply, Delivery, Receiving, Setup, Installation and Commissioning.

6.8 Title

The Design-Builder will cause the procurement arrangements for Category 1 Equipment to provide for a direct transfer of title to such Equipment from the vendors to the Authority. Title to Category 1 Equipment may be reserved by third party unpaid vendors until the earlier of the date of payment and the Target Building Substantial Completion Date. The Design-Builder will pay all such unpaid vendors prior to the Target Building Substantial Completion Date for amounts owing on outstanding invoices.

6.9 Damage and Loss

Any damage or loss occurring prior to the Target Building Substantial Completion Date to:

- (a) Category 2 Equipment or Category 1 Equipment after it has been Received; or
- (b) Category 3 Equipment or Category 4 Equipment after it is Installed if it is installed prior to the Target Building Substantial Completion Date,

is the responsibility of the Design-Builder.

6.10 Acceptance Protocol

A document will be provided by the Design-Builder to the Authority for each Category 2 and Category 1 item that certifies all testing of the relevant Equipment has been completed to demonstrate that it has been installed in accordance with the manufacturer's requirements and is functioning in accordance with the specifications included in the relevant equipment purchase contract or purchase order (the "Acceptance Protocol").

Without limiting the Design-Builder's obligation to Commission the relevant Equipment, the Design-Builder will, to the Authority's reasonable satisfaction, complete all of the aspects of the Acceptance Protocol for each item of Category 2 and Category 1 Equipment.
If:

- (a) prior to the Target Building Substantial Completion Date, the Design-Builder fails to complete any aspect of an Acceptance Protocol for any item of Category 2 or Category 1 Equipment; and
- (b) the Authority waives the requirement for the Design-Builder to complete the relevant Acceptance Protocol prior to the Target Building Substantial Completion Date, then subject to meeting the other requirements for Substantial Completion of the Building each such failure will be a deficiency and the Authority may make the withholding described in Section 44.5(b) of the Design-Build Agreement.

6.11 Equipment Logistics Schedule

The Design-Builder will propose a draft schedule (the "Equipment Logistics Schedule") within 30 days after the Effective Date and the parties will seek to finalize the Equipment Logistics Schedule, each party acting reasonably, within 90 days after the Effective Date, in accordance with the following principles:

- (a) in order to take advantage of the most recent technological advances, final decisions on the selection of Equipment sensitive to or anticipated to be revised with newer technology

prior to the Target Building Substantial Completion Date, together with any training or service requirements, will not be made by the Authority until as late as possible in the period for Construction;

- (b) the Design-Builder will require adequate time to issue competitive bidding documents, receive proposals, clarify aspects of proposals, and Receive, Install and Commission the Equipment;
- (c) the Authority will require the ability to take advantage of bulk or other purchase opportunities advantageous to it; and
- (d) the Design-Builder will undertake the precautions set out by Equipment vendors to protect any Equipment that is required to be Delivered or Installed while construction is still underway; however, as an additional precaution some sensitive Equipment (such as medical devices and equipment with electronic components) may require Delivery, Installation and Commissioning dates that are late in the period for Construction.

The parties may modify the Equipment Logistics Schedule by mutual agreement, each acting reasonably.



Musson Cattell Mackey Partnership

1600-555 Burrard Street, Vancouver. V7X 1M9
tel 1.604 687 2990

Equipment Key.

The following is an explanation of Columns in the Equipment List.
It should be noted that the List includes all Items of Equipment for which a space name is allocated.
External Equipment is not always listed.

The List includes Equipment assigned to Groups 1, 2, 3 and 4. (As described below)

Groups 1 and 2 include items that are usually provided and installed under contract by the General Contractor such as Millwork, Electrical fixtures etc. These are listed for your convenience but Proponents must satisfy themselves that provided quantities are correct.

Column	Description
ID	Individual Database generated ID Number.
Group	Group 1. – Supplied and Installed By Design Build Team Group 2. – Supplied by Northern Health and Installed by Design Build Team. Group 3. - Supplied and Installed by Northern Health. Group 4. - Relocated from the Existing Hospital to the New Hospital By Northern Health.
Division (Div.)	Equipment is loosely Broken down by Division and section following the Master Format system. The numbers used herein have been adapted to work with the software used.
Code	An Abbreviation Code given to each Equipment Item to help with item identity. Codes Appear on 1:50 Fit-Out Plans and in Room Data Sheets. The Kit of Parts is a graphical representation of what is required for all Fabricated Items and some Proprietary items. The Kit of Parts does not include every Item listed in the Schedule.
Description	A Written Description of the Equipment Item
No.	The Quantity of the particular Item used or required in the project. Proponents must satisfy themselves that numbers are accurate.
Note	This column is used to help identify item requirements. Proponents may be referred to Cut Sheets, Specifications of another document.

Equipment Key



Musson Cattell Mackey Partnership

1600-555 Burrard Street, Vancouver. V7X 1M9
tel 1.604 687 2990

Key to Division Codes

No	Description	No	Description
9680	Carpet	8210	Wood Doors
9650	Resilient Finishes	8120	Aluminum Doors & Frames
9440	Epoxy Terrazzo Flooring	8110	Hollow Metal Doors & Frames
12345	Casework	8351	Sliding Folding Grilles
10190	Hospital Cubicle Tracks	12510	Window Coverings
10800	Fixtures	6100	Rough Carpentry
5500	Metalwork	16005	Electrical - Communications
10100	White Boards & Tack boards	16010	Electrical - Power
10805	Washroom Accessories	16015	Electrical - Fire
5700	Stainless Steel	16025	Electrical - Lighting
9250	Ceilings	16020	Electrical - Security
6400	Arch Woodwork Floor Plans	15010	Mechanical
6430	Arch Woodwork Ceilings	15015	Plumbing
6410	Arch Woodwork Fitout Plans	13930	Sprinklers
9960	Vinyl Wall Coverings	15005	Medical Gases
9251	Partitions	20000	IMIT Equipment
9965	Special Wall Coverings	30001	FFE
10260	Wall Guards & Protection	40001	Facilities Management
9900	Painting	50001	Kitchen Equipment
8510	Internal Windows & Glazing	60001	Medical Specialist
8450	Aluminum Storefronts	99999	Trade Section Pending
10650	Operable Partitions	100000	Architectural Equipment Medical Specialist
8350	Accordion Doors		

Equipment Key

ID	Grp	Div.	Code	Description	No	Notes
41275	1	5700	BH600SSF	Bench - High: 600dp; Stainless Steel - Flat	3	Fabricated Item
41276	1	5700	BH600SSM	Bench - High: 600dp; Stainless Steel - Marine Edge	5	Fabricated Item
41279	1	5700	BH750SSM	Bench - High: 750dp; Stainless Steel - Marine Edge	1	Fabricated Item
41627	1	5700	BH900SSFF	Bench - High: 900dp; Stainless Steel - Flat Edge; Free Standing Island.	1	Fabricated Item
41674	1	5700	HRSS	Hand Rail - Stainless Steel Tube	4	Fabricated Item
41588	1	5700	LEGSS	Stainless Steel leg	6	Fabricated Item
40906	1	5700	PFSSKD	Stainless Steel - Integral Stainless Steel Double Bowl Sink 450l x 400d x 200h.	3	Refer Specifications
40907	1	5700	PFSSKS	Stainless Steel - Integral Stainless Steel Single Bowl Sink	2	Refer Specifications
41129	1	5700	SSSB	Stainless Steel Splashback	8	Fabricated Item
41416	1	6400	BH350L	Bench - High: 350dp w/ Laminate Finish	1	Fabricated Item
41438	1	6400	BH450L	Bench - High: 450dp w/ Laminate Finish	6	Fabricated Item
41263	1	6400	BH600L	Bench - High: 600dp w/ Laminate Finish	29	Fabricated Item
41266	1	6400	BH750L	Bench - High: 750dp w/ Laminate Finish	13	Fabricated Item
41290	1	6400	BH750W	Bench - High - 750dp Wood Workbench	1	Fabricated Item
41672	1	6400	BHLPHONE	Bench - High & Low Public Telephone Counter	1	Fabricated Item
41599	1	6400	BL300L	Bench - Low: 300dp w/ Laminate Finish	1	Fabricated Item
41462	1	6400	BL450L	Bench - Low: 450dp w/ Laminate Finish	1	Fabricated Item
41264	1	6400	BL600L	Bench - Low: 600dp w/ Laminate Finish	1	Fabricated Item
41267	1	6400	BL750L	Bench - Low: 750dp w/ Laminate Finish	23	Fabricated Item
41361	1	6400	BL900L	Bench - Low: 900dp w/ Laminate Finish	2	Fabricated Item
40029	1	6400	BS2	Bench Seat - Vinyl Padded	1	Fabricated Item
41622	1	6400	BSFD1	Bedside Fixed Dresser Chamfered 600 x 450 .	6	Fabricated Item
41623	1	6400	BSFDL	Bedside Fixed Dresser Chamfered Right Hand.	2	Fabricated Item
41581	1	6400	BSG5	Bed Side Gas Unit - Infant Rescussitation Cupboard	1	Fabricated Item
41582	1	6400	BSG6	Bed Side Gas Unit - Mothers Rescussitation Cupboard	1	Fabricated Item
41649	1	6400	BSG7L	Bed Side Gas Unit - Mothers Refrigerator Cupboard; Left Handed	1	Fabricated Item
41561	1	6400	BV13	Bench Vanity - 500 Deep for Fully Recessed Basin One Free End	3	Fabricated Item
41563	1	6400	BV21	Bench Vanity - 350 Deep for Semi Recessed Basin	1	Fabricated Item
41566	1	6400	BV25	Bench Vanity - 350 Deep for Semi-Recessed Basin; Corner Unit.	17	Fabricated Item
41262	1	6400	BX600L	Bench - Extra High: 600dp w/ Laminate Finish	2	Fabricated Item
40143	1	6400	CRS	Clothes Rail & Shelf Laminate Finish 300 Deep at 1800 High	2	Fabricated Item
40146	1	6400	CU1	Tall Cup'd Unit - without doors	3	Fabricated Item
41617	1	6400	CU104/1	Patient Records and Form Unit	1	Fabricated Item
41644	1	6400	CU105	Tall Cup'd Unit - Mop and Broom Cupboard	1	Fabricated Item
41677	1	6400	CU106	Tall Cup'd Unit - Pharmacy Dispensary ??U? Shelving.	3	Fabricated Item
41679	1	6400	CU107	Tall Cup'd Unit - Pharmacy Dispensary? Shelving 300 deep.	1	Fabricated Item

ID	Grp	Div.	Code	Description	No	Notes
41680	1	6400	CU108sm	Tall Cup'd Unit - Pharmacy Dispensary? Shelving Site Measured Width 200 deep.	4	Fabricated Item
40158	1	6400	CU2	Tall Cup'd Unit - Without Doors	3	Fabricated Item
41633	1	6400	CU28	Tall Cup'd Unit - Linen Service Cupb w/- Upper & Lower Doors	4	Fabricated Item
40167	1	6400	CU2sm	Tall Cup'd Unit - Without Doors Site Measured	42	Fabricated Item
40168	1	6400	CU3	Tall Cup'd Unit - With Single Door	4	Fabricated Item
40169	1	6400	CU3sm	Tall Cup'd Unit - With Single Door Site Measured	2	Fabricated Item
40170	1	6400	CU4	Tall Cup'd Unit - with Double Doors	2	Fabricated Item
41635	1	6400	CU4PT	Tall Cup'd Unit - Pass Through Cupboard; Glass Doors Both Sides	6	Fabricated Item
40171	1	6400	CU4sm	Tall Cup'd Unit - with Double Doors Site Measured	6	Fabricated Item
41305	1	6400	RCSS	Reception / Transaction Counter 1050 High Solid Surfacing	15	Fabricated Item
41612	1	6400	S300L	Shelf - Plastic Laminatel Finish 300 Deep at 1500 High	1	Fabricated Item
41647	1	6400	S500L	Shelf - Plastic Laminatel Finish 500 Deep at 1500 High.	1	Fabricated Item
41301	1	6400	WR2	Wardrobe Unit - Fixed Shelf & Hang Space 450 wide Right	3	Fabricated Item
41351	1	6400	WR2L	Wardrobe Unit - Fixed Shelf & Hang Space 450 wide Left	8	Fabricated Item
41648	1	6400	WR5L	Wardrobe - Fixed Shelf & Hang Space 600 wide. Left Hand.	1	Fabricated Item
41516	1	6400	WR6L	Wardrobe Unit - Double Doors; Chamfer on one side; Fixed Shelf & Hang Space 600 wide. Left Hand.	2	Fabricated Item
41621	1	6400	WR6R	Wardrobe Unit - Double Doors; Chamfer on one side; Fixed Shelf & Hang Space 600 wide. Right Hand.	6	Fabricated Item
41243	1	6400	WRPS	Wardrobe Unit - Psych Fixed Shelf & Collapsible Hooks 450 wide	1	Fabricated Item
40003	1	6410	BBAsm	Bed Buffer - Acrovyn Headwall Protection Site Measured	27	Fabricated Item
41687	1	6410	BBPLsm	Bed Buffer - P Lam Headwall Protection Site Measured	8	Fabricated Item
40005	1	6410	BBWsm	Bed Buffer - Wood Headwall Protection Site Measured	18	Fabricated Item
40052	1	6410	CBR450	Cantilever Counter Bracket - 450dp bench	6	Fabricated Item
40053	1	6410	CBR600	Cantilever Counter Bracket - 600dp bench	4	Fabricated Item
40054	1	6410	CBR750	Cantilever Counter Bracket - 750dp bench	13	Fabricated Item
40055	1	6410	CE	Cable Entry Grommit in Counter	68	Proprietry Item
41634	1	6410	DRESSER	Dresser - Long Term Resident Dresser Unit	8	Fabricated Item
40388	1	6410	EPL750	Millwork - End Support Panel Under 750dp Low Bench	2	Fabricated Item
41624	1	6410	FXPIB	Fixture - Personalized Identification Board	7	Fabricated Item
40593	1	6410	HRW	Hand Rail - Solid Wood Handrail	59	Fabricated Item
40654	1	6410	LSB	Laminated Panel Backsplash	17	Fabricated Item
41486	1	6410	LSBHB	Laminated Panel Backsplash to Hand Basin	48	Fabricated Item

ID	Grp	Div.	Code	Description	No	Notes
40674	1	6410	MBTOBL	Media Board - Tack Over Bench Low	1	Fabricated Item
41362	1	6410	OB2	OB Cup'd - Without Doors	4	Fabricated Item
40813	1	6410	OB2sm	OB Cup'd - No Doors Site Measured	3	Fabricated Item
41620	1	6410	OB31TV	OB Cup'd - Recessed 31 TV Wall Box. Lexan Faced	1	Fabricated Item
40817	1	6410	OB32	OB Cup'd - Folder Storage no Door 900w	24	Fabricated Item
40818	1	6410	OB32sm	OB Cup'd - Form Storage no Doors Site Measured	16	Fabricated Item
40828	1	6410	OB3sm	OB Cup'd - With Door Site Measured	5	Fabricated Item
40829	1	6410	OB4	OB Cup'd - With Doors 900w	2	Fabricated Item
41579	1	6410	OB40	OB Cup'd - Delivery Room Equipment Shelf 350 Deep	3	Fabricated Item
40836	1	6410	OB46	OB High Cup'd - Rangehood Unit 900w	2	Fabricated Item
40840	1	6410	OB4sm	OB Cup'd - With Doors Site Measured	13	Fabricated Item
40844	1	6410	OB52	OB Cup'd - Counter Top Form Storage 675w	5	Fabricated Item
41574	1	6410	OB6sm	OB Cup'd - Medications Lockable Doors Site Measured Width	3	Fabricated Item
40849	1	6410	OB9	OB Cup'd - Microwave Oven 600w	4	Fabricated Item
41685	1	6410	OBSC	OB Unit - Mirrored Shaving Cabinet	8	Refer Specification
40853	1	6410	PEG1	Peg Rack Type 1 - 200 Centres	3	Fabricated Item
40979	1	6410	PLYP	Plywood Panel - 19mm GIS rated	14	Fabricated Item
41168	1	6410	TVC4	TV Cabinet Type 4 - Floor Unit Chamfered w/ Doors	1	Fabricated Item
41185	1	6410	UBH1	UB High Cup'd - No Door 450 wide	1	Fabricated Item
41186	1	6410	UBH11	UB High Cup'd - 3 Drawers 1 Hang File	2	Fabricated Item
41188	1	6410	UBH19	UB High Cup'd - X-Ray Storage Slots 500 wide	1	Fabricated Item
41189	1	6410	UBH1sm	UB High Cup'd - No Door Site Measured	3	Fabricated Item
41190	1	6410	UBH2	UB High Cup'd - No Doors 900 wide	3	Fabricated Item
41191	1	6410	UBH22	UB High Cup'd - Trash Bin Unit	4	Fabricated Item
41195	1	6410	UBH2sm	UB High Cup'd - No Doors Site Measured	3	Fabricated Item
41196	1	6410	UBH3	UB High Cup'd - With Door 450 wide	3	Fabricated Item
41197	1	6410	UBH3sm	UB High Cup'd - With Door Site Measured	12	Fabricated Item
41198	1	6410	UBH4	UB High Cup'd - With Doors 900 wide	14	Fabricated Item
41199	1	6410	UBH4sm	UB High Cup'd - With Doors Site Measured	30	Fabricated Item
41200	1	6410	UBH5	UB High Cup'd - With Door & Drawer	1	Fabricated Item
41201	1	6410	UBH5sm	UB High Cup'd - With Door & Drawer Site Measured	6	Fabricated Item
41203	1	6410	UBH6sm	UB High Cup'd - With Doors & Drawers Site Measured	4	Fabricated Item
41204	1	6410	UBH9	UB High Cup'd - 4 Equal Drawers	11	Fabricated Item
41205	1	6410	UBH9sm	UB High Cup'd - 4 Equal Drawers Site Measured	4	Fabricated Item
41219	1	6410	UBHL	Underbench High Leg - 1200 Centres Max	20	Fabricated Item
41208	1	6410	UBL11	UB Low Cup'd - 2 Drawers & Hang File 450 Wide	2	Fabricated Item
41212	1	6410	UBL3	UB Low Cup'd - With Door 450 wide	4	Fabricated Item
41512	1	6410	UBL31	UB Low Cup'd - With Two Lockable Hangfile Drawers	8	Fabricated Item
41215	1	6410	UBL4sm	UB Low Cup'd - With Doors Site Measured	1	Fabricated Item

ID	Grp	Div.	Code	Description	No	Notes
41667	1	6410	UBL6sm	UB Low Cup'd - With Doors & Drawers Site Measured	1	Fabricated Item
41218	1	6410	UBL9	UB Low Cup'd - 4 Equal Drawers	2	Fabricated Item
41671	1	6410	UBLANK	UB Blank Panel	7	Fabricated Item
41220	1	6410	UBLM11	UB Mobile Low Cup'd - 2 Drawers & Hang File	25	Fabricated Item
41228	1	6410	UBX4	UB X-High Cup'd - With Doors	4	Fabricated Item
41240	1	6410	WBA	Wall Buffer Acrovyn - Acrovyn Sheet to Wall	205	Fabricated Item
41412	1	6410	WBA1400	Wall Buffer Acrovyn - Acrovyn Sheet to 1400 high	43	Fabricated Item
41241	1	6410	WBW	Wall Buffer Wood - Solid Wood Buffer	318	Fabricated Item
40701	1	6430	MDFB	Bulkhead - Medium Density Fibreboard Over Millwork to Ceiling	85	Fabricated Item
41336	1	8510	IWA	Internal Window - Type A - 2150 Head x 50 Sill	23	Fabricated Item
41337	1	8510	IWB	Internal Window - Type B - 2150 Head x 200 Sill	3	Fabricated Item
41339	1	8510	IWD	Internal Window - Type D - 2150 Head x 900 Sill	15	Fabricated Item
41586	1	8510	IWDS	Internal Window - Type D - 2150 Head x 900 Sill Sliding Glass	1	Fabricated Item
41343	1	8510	IWH	Internal Window - Type H - 2150 Head x 1100 Sill	2	Fabricated Item
41689	1	9250	CFMFT	Ceiling Feature Minearl Fibre Tile	12	Fabricated Item
40852	1	9250	PBCB	Gypsum Board Bulkhead	16	Fabricated Item
40549	1	10190	FXCT	Fixture - Curtain Track Patient Bedscreen Track	33	Proprietary System as specified
40552	1	10190	FXCTSHR	Fixture - Curtain Track Shower Cubicle	18	Proprietary System as specified
40560	1	10190	FXPLS	Fixture - Patient Lift Ceiling Tracks - One Traversing Rail; 600 lb Bariatric Rated.	23	Angel Lift Systems or Equal
41646	1	10190	FXPLSCR	Fixture - Patient Lift Track; Single Ceiling Rail. 600 lb Bariatric Rated.	1	Angel Lift Systems or Equal
40561	1	10190	FXPLTS	Fixture - Patient Lift Motor including Sling and Accessories.	24	Angel C625 Fixed Motor with Universal Sling
40547	1	10260	FXCG14	Fixture - Corner Guard 1400 High; 75 x 75	165	Acrovyn Corner Guard with Aluminum Angle Base and end caps, as specified.
40546	1	10260	FXCG14A	Fixture - Corner Guard - 135d Corner 1400 High x 75 x 75	20	Acrovyn Corner Guard with Aluminum Angle Base and end caps, as specified.
40197	1	10800	DISCMS	Dispenser - Cleaners Chemical Management System	4	Northern Health Standard at Time of order
41675	1	10800	FX6BIKR	Fixture - 6 Place SS Bicycle Rack	2	Global Industries Stadium 6 Bike Rack
40532	1	10800	FXBCSV	Fixture - Baby Change Station - Vertical	5	Northern Health Standard at Time of order
41773	1	10800	FXBPLD	Fixture - Bedpan Liner Dispenser - Vernacare V30-005 Bedpan Liner dispenser Rack	3	Vernacare V30-005 Bedpan Liner dispenser Rack
41772	1	10800	FXBPSR	Fixture - Bedpan Support Rack - Vernacare V30-010 Bedpan Support Rack.	3	Vernacare V30-010 Bedpan Support Racks
41771	1	10800	FXBPUR	Fixture - Bedpan Urinal Rack - Vernacare V30-016 Urinal Rack	3	Vernacare V30-016 Vernacare Urinal Rack

ID	Grp	Div.	Code	Description	No	Notes
40544	1	10800	FXBSB	Fixture - Bracket - Suction Bottle Bracket	32	Northern Health Standard at Time of order
41673	1	10800	FXDEFWB	Fixture - Defibrillator Semi Recessed Wall Cabinet with Alarm	2	Lifepak 500
41618	1	10800	FXPCH	Fixture - Patient Ceiling Hook	2	Fabricated Item, as detailed in Indicative Design
41526	1	10800	FXPHAPT	Fixture - Pharmacy Pass Through Airlock Hatch.	3	Market Lab ML3190 Pass Through Locking Specimen Cabinet. 12" x 5"d x 11.25" Inside dimensions.
40568	1	10800	FXTVBC	Fixture - Bracket Television Ceiling Bracket	10	Northern Health Standard at Time of order
41619	1	10800	FXTVFWB	Fixture - Bracket Fixed Television Wall Mounted	17	Northern Health Standard at Time of order
41764	1	10800	FXWBC	Fixture - Bracket - Wall Mounted Bracket for Computer Station (SSM IT Station)	15	Amico IT Station with 12" Extension
40585	1	10800	GR11AB	Grabrail - Both Sides of Patient Toilet	10	Refer Specification
40586	1	10800	GR2	Grabrail - 600 Long	14	Refer Specification
40588	1	10800	GR4	Grabrail - Disabled	5	Refer Specification
40589	1	10800	GR5	Grabrail - Patient Toilet - Inclined	12	Refer Specification
40590	1	10800	GR6	Grabrail - Patient Shower Grabrail	11	Refer Specification
40655	1	10800	M1	Mirror - 650h x 500w	11	Proprietary Item - Bobrick or Equal
40657	1	10800	M3	Mirror - 1500 x 500w	19	Proprietary Item - Bobrick or Equal
40658	1	10800	M4	Mirror - 900h x 500w	9	Proprietary Item - Bobrick or Equal
41291	1	10800	M4PS	Mirror - 900h x 500w Polished Metal Psychiatric	1	Refer Equipment Cut Sheets
40659	1	10800	M5	Mirror - 950h x 500w Tilted	8	Proprietary Item - Bobrick or Equal
40660	1	10800	M6	Mirror - 900h x 600w	3	Proprietary Item - Bobrick or Equal
40664	1	10800	MBT1200	Media Board - Tack 1200 Long	3	Refer to Indicative Design Specification
40665	1	10800	MBT1500	Media Board - Tack 1500 Long	1	Refer to Indicative Design Specification
40666	1	10800	MBT1800	Media Board - Tack 1800 Long	3	Refer to Indicative Design Specification
40669	1	10800	MBT900	Media Board - Tack 900 Long	19	Refer to Indicative Design Specification
40672	1	10800	MBTH900	Media Board - Tack High 900 long	11	Refer to Indicative Design Specification
40675	1	10800	MBW1200	Media Board - White Board 1200 long	3	Refer to Indicative Design Specification
40677	1	10800	MBW1800	Media Board - White Board Magnetic 1800 long	3	Refer to Indicative Design Specification
41706	1	10800	MBW2400	Media Board - White Board Magnetic 2440 long	1	Refer to Indicative Design Specification
41688	1	10800	MBW350	Media Board - White Board 350 long	8	Refer to Indicative Design Specification
40679	1	10800	MBW600	Media Board - White Board 600 long	6	Refer to Indicative Design Specification

ID	Grp	Div.	Code	Description	No	Notes
40680	1	10800	MBW900	Media Board - White Board 900 long	29	Refer to Indicative Design Specification
40781	1	10800	MXA	Maxi Bin Storage Panel 457w X 1830h	15	Dexion Louvered Panel for Plastic Storage Bins.
41591	1	10800	PHCG	Physiotherapy - Ceiling Mounted Grid	1	Fabricated Item, as detailed in Indicative Design
41590	1	10800	PHWG	Physiotherapy - Wall Mounted Grid	1	Fabricated Item, as detailed in Indicative Design
40988	1	10800	RACKM	Rack - Magazine Rack	2	Northern Health Standard at Time of order
40989	1	10800	RACKP	Rack - Pamphlet Rack	2	Northern Health Standard at Time of order
40023	1	10805	BINSDL	Bin - Sharps Disposal Large - Wall Mounted	2	Northern Health Standard at Time of order
40024	1	10805	BINSDS	Bin - Sharps Disposal Small - Wall Mounted	58	Northern Health Standard at Time of order
40194	1	10805	DISACD	Dispenser - Alcohol Chlorhexadine Dispenser	4	Northern Health Standard at Time of order
40198	1	10805	DISGD	Dispenser - Glove: 4 Sizes	66	Northern Health Standard at Time of order
40200	1	10805	DISPD	Dispenser - Paper Towel	96	Northern Health Standard at Time of order
40202	1	10805	DISSD	Dispenser - Soap Dispenser	96	Northern Health Standard at Time of order
40204	1	10805	DISTPD	Dispenser - Toilet Paper Dispenser	38	Northern Health Standard at Time of order
41324	1	10805	DISTPDR	Dispenser - Toilet Paper Dispenser Recessed Psychiatric	2	Northern Health Standard at Time of order
40555	1	10805	FXHK	Fixture - Hook - Standard Hat & Coat	227	Refer Specification
40556	1	10805	FXHKC	Fixture - Hook - Collapsible	2	Northern Health Standard at Time of order
40562	1	10805	FXPS	Fixture - Proprietary Mirror Shelf	11	Refer Specification
40563	1	10805	FXPSH	Fixture - Proprietary Soap / Shampoo Shelf	15	Northern Health Standard at Time of order
41327	1	10805	FXRSH	Fixture - Recessed Soap Holder	1	Refer Specification
40566	1	10805	FXTR	Fixture - Towel Rail	1	Bobrick B-530 x 18 - Extra Heavy Duty Surface Mounted Towel Bar. http://www.bobrick.com/washroomaccessories/Pages/ProductDetails.aspx?Product+Number%3dB-530+x+18
40663	1	10805	MBRP	Mop & Broom Rack - Proprietary	3	Northern Health Standard at Time of order
41699	1	12345	BH1200LABF	Bench - 900 High - 1200dp Laboratory Grade; Free Standing	1	Fabricated Item
41703	1	12345	BH1500LABF	Bench - 900 High - 1500dp Laboratory Grade; Free Standing	1	Fabricated Item
41285	1	12345	BH750LAB	Bench - High - 750 dp; Laboratory Grade	3	Fabricated Item
41389	1	12510	WTBBL	Window Treatment - Blackout Roller Blinds	4	Northern Health Standard at Time of order
40740	1	15005	MGAP	Medical Gas - Alarm Panel	3	Amico

ID	Grp	Div.	Code	Description	No	Notes
40742	1	15005	MGASCW	Medical Gas - Anaesthetic Scavenging - Wall Mounted	1	Amico
40745	1	15005	MGHGP3	Medical Gas - Hinged Lockable Gases Panel Cover	1	Amico
40746	1	15005	MGIV	Medical Gas - Isolation Valve	3	Amico
40747	1	15005	MGMAP	Medical Gas - Medical Air Pendant/Boom Mounted	2	Amico
40748	1	15005	MGMAW	Medical Gas - Medical Air Wall Mounted	34	Amico Console Unit
40752	1	15005	MGNOW	Medical Gas - Nitrous Oxide From Cylinder	1	Northern Health Standard at Time of order
40754	1	15005	MGOXP	Medical Gas - Oxygen Pendant/ Boom Mounted	2	Amico
40755	1	15005	MGOXW	Medical Gas - Oxygen Wall Mounted	34	Amico Console Unit
40757	1	15005	MGSUP	Medical Gas - Suction Pendant/ Boom Mounted	2	Amico
40758	1	15005	MGSUW	Medical Gas - Suction Wall Mounted	33	Amico Console Unit
41735	1	15010	SBGEN	Stand-By Diesel Fueled Generator Set - Refer Mechanical	2	Refer Specifications
41709	1	15010	SPCAB	Sprinkler Control Cabinet	2	Refer Specifications
40187	1	15015	DADW	Domestic Appliance - Underbench Dishwasher	7	Miele Domestic Dishwasher
40612	1	15015	KITICBT	Kitchen - Ice Maker Counter Top	2	Symphony Ice and Water Dispensor - 12 Series Compat Counter Top Unit
40687	1	15015	MCBPMF	Medical Cleaning Equipment - Bed Pan Maserater Free Standing - Vernacare	3	Vernacare V40-400ef1
41692	1	15015	PFBATHAP	Plumbing Fixture - Peninsula Arjo-Parker Side Opening Bath.	1	Arjo Parker Bath' Refer Cut Sheet.
40856	1	15015	PFBATHDL	Plumbing Fixture - Domestic Bath Against Wall Left Handed	1	Refer Specifications
41577	1	15015	PFBATHPD	Plumbing Fixture - Bath Delivery; Patient Peninsula	1	Refer Specifications
40860	1	15015	PFCSF	Plumbing Fixture - Cleaners Sink Floor Mounted Stainless Steel	4	Refer Specifications
41543	1	15015	PFETDH	Plumbing Fixture - Emergency Tempered Drench Hose & Eye Wash	2	Refer Specifications
41252	1	15015	PFHB1	Plumbing Fixture - Clinical Handwash Basin.	39	Refer Specifications
41254	1	15015	PFHB2	Plumbing Fixture - Medium Size Handwash Basin	8	Refer Specifications
40871	1	15015	PFHB3	Plumbing Fixture - Patient & Public Small Handwash Basin w/ Standard Taps & Outlet	11	Refer Specifications
41631	1	15015	PFHB5	Plumbing Fixture - Hair Dressing Basin Wall Mounted	1	Refer Specifications
41616	1	15015	PFHBPSY	Plumbing Fixture - Pyschiatric Penal SS Handbasin	1	Refer Specifications
40885	1	15015	PFHBVFR	Plumbing Fixture - Hand Basin Vanity Fully Recessed Basin	4	Refer Specifications
40905	1	15015	PFHBVSR	Plumbing Fixture - Hand Basin Vanity Semi Recessed Basin	17	Refer Specifications
40887	1	15015	PFSCRUB1	Plumbing Fixture - Scrub Trough Single Bay Proprietary SS Station with SensorTap	4	Refer Specifications
40893	1	15015	PFSHED	Plumbing Fixture - Emergency Deluge Shower	1	Refer Specifications

ID	Grp	Div.	Code	Description	No	Notes
40894	1	15015	PFSHP	Plumbing Fixture - Shower: Ambulant Patient - Fixed Head	5	Refer Specifications
40895	1	15015	PFSHPA	Plumbing Fixture - Shower Patient Assisted	1	Refer Specifications
41299	1	15015	PFSK1	Plumbing Fixture - Inset SS Sink - Single Bowl	2	Refer Specifications
41451	1	15015	PFSK2S	Plumbing Fixture - Inset SS Sinks Double Bowl Small	9	Fabricated Item
40900	1	15015	PFSKL	Plumbing Fixture - Inset SS Sink - Small Laboratory	2	Fabricated Item
40919	1	15015	PFWBS	Plumbing Fixture - Over Head Water Boiler Small	6	Refer Specifications
41298	1	15015	PFWCD	Plumbing Fixture - Toilet Standard Accessable / Disabled	5	Refer Specifications
40929	1	15015	PFWCP	Plumbing Fixture - Toilet Patient Standard	22	Refer Specifications
40934	1	15015	PFWCPN	Plumbing Fixture - Toilet Secure Psych (Penalware)	1	Refer Specifications
40936	1	15015	PFWCS	Plumbing Fixture - Toilet Standard Ambulant	11	Refer Specifications
41698	1	15015	PFWCSSPS	Plumbing Fixture - Toilet Secure Stainless Steel Psych	1	Refer Specifications
41259	1	15015	PL100BHD	Plumbing - 100mm Blade Handles Deck Mounted	18	Refer Specifications
40946	1	15015	PL100BHW	Plumbing - 100mm Blade Handle Mixer Tap Wall Mounted	18	Refer Specifications
40947	1	15015	PL40LHD	Plumbing - 40mm Lever Handles Deck Mounted	32	Refer Specifications
40948	1	15015	PL40LHW	Plumbing - 40mm Lever Handles Wall Mounted	3	Refer Specifications
41578	1	15015	PLBDSW	Plumbing - Bath Diverter Spout; Wall Mounted.	2	Refer Specifications
41861	1	15015	PLEDP	Plumbing - Equipment Drain Connection	1	Refer Specifications
40953	1	15015	PLFD	Plumbing - Floor Drain	37	Refer Specifications
40954	1	15015	PLFGS	Plumbing - Fixed Goose Neck Spout	11	Refer Specifications
40956	1	15015	PLFSH	Plumbing - Fixed Shower Head	1	Refer Specifications
40961	1	15015	PLHS	Plumbing - Hand Held Flexible Shower on Sliding Grab Rail	13	Refer Specifications
41632	1	15015	PLHSO	Plumbing - Hand Held Flexible Shower Outlet - Basin Mounted	1	Refer Specifications
40963	1	15015	PLPT	Plumbing - Plaster Trap	1	Refer Specifications
40965	1	15015	PLSAOD	Plumbing - Sensor Activated Outlet Deck Mounted	48	Refer Specifications
40968	1	15015	PLSGNOD	Plumbing - 230mm High Goose Neck Swivel outlet (Deck Mounted)	17	Refer Specifications
41296	1	15015	PLSGSD	Plumbing - Swivel Goose Neck Spout Deck Mounted	21	Refer Specifications
40970	1	15015	PLSTP	Plumbing - Sewer Termination Point	127	Refer Specifications
40973	1	15015	PLWFS	Plumbing - Washing Machine Faucet Set	3	Refer Specifications
40974	1	15015	PLWMSF	Plumbing - Wall Mounted Service Faucet	3	Refer Specifications
40976	1	15015	PLWTPC	Plumbing - Cold Water Termination Point	168	Refer Specifications
40977	1	15015	PLWTPH	Plumbing - Hot Water Termination Point	11	Refer Specifications
40978	1	15015	PLWTPT	Plumbing - Tepid Water Termination Point	117	Refer Specifications
40116	1	16005	COMI	Comm - Intercom Station Outlet	19	Refer Specification
41875	1	16005	COMMRFID	Comm - RFID Outlet - Wall	5	Refer Specification

ID	Grp	Div.	Code	Description	No	Notes
40129	1	16005	COMT	Comm - Telephone Outlet - Wall	312	Refer Specification
41766	1	16005	COMTC	Comm - Telephone Outlet - Ceiling	11	Refer Specification
40134	1	16005	COMTP	Comm - Data Point - Public Telephone Outlet	3	Refer Specification
40137	1	16005	COMTVO	Comm - Television Outlet - Wall	24	Refer Specification
40138	1	16005	COMTVOC	Comm - Television Outlet - Ceiling Mounted	8	Refer Specifications
40786	1	16005	NCC	Nurse Call - Patient Call Station - Pushbutton	37	Refer Specifications
40787	1	16005	NCCB	Nurse Call - Code Blue Call Station - Pushbutton	32	Refer Specifications
40788	1	16005	NCCDL	Nurse Call - Dome Indicator Light - Common/ Corridor	14	Refer Specifications
41736	1	16005	NCCZL	Nurse Call - Ceiling Mounted Zone Light	8	Refer Specifications
41763	1	16005	NCEBB	Nurse Call - Equipotential Bonding Bus	24	Refer Specifications
40793	1	16005	NCECC	Nurse Call - Patient Emergency Call Station - Pull Cord	75	Refer Specifications
40794	1	16005	NCECCWP	Nurse Call - Patient Emergency Nurse Call Station - Pull Cord (Waterproof)	14	Refer Specifications
40796	1	16005	NCECS	Nurse Call - Staff Emergency Call Station - Push Button	45	Refer Specifications
40800	1	16005	NCMS	Nurse Call - Master Control Station	4	Refer Specifications
41737	1	16005	NCSDTs	Nurse Call - Staff Duty Station/Tone Station	13	Refer Specifications
41734	1	16005	NCWCDL	Nurse Call - Wall Mounted Nurse Call Dome Light	42	Refer Specifications
41762	1	16010	ELDHS	Lighting - Dimmer Switch	30	Refer Specifications
41732	1	16010	ELLVS	Lighting - Line Voltage Switch	68	Refer Specifications
41761	1	16010	ELLVWMOSS	Lighting - Line Voltage Wall Mounted Occupancy Sensor Switch	26	Refer Specifications
41760	1	16010	ELOLVS	Lighting - One Low Voltage Switch	129	Refer Specifications
40334	1	16010	ELSWDM	Lighting - Dimmer Switch	56	Refer Specifications
41757	1	16010	ELTHLVS	Lighting - 2 Line Voltage Switch	14	Refer Specifications
41733	1	16010	ELTLVS	Lighting - 2 Line Voltage Switch	60	Refer Specifications
40389	1	16010	EPBASIC	Electrical - Special Receptacle	3	Refer Specifications
40392	1	16010	EPCLS	Electrical - Standard Clock Wall Mounted (Unsynchronised)	12	Refer Specifications
40394	1	16010	EPCLS2W	Electrical - Synchronise Clock Wall Mounted Two Faced	14	Refer Specifications
40396	1	16010	EPCLSW	Electrical - Synchronise Clock Single Face Wall Mounted .	59	Refer Specifications
40397	1	16010	EPCLTE	Electrical - Clock Time Elapse Wall Mounted	2	Refer Specifications
40402	1	16010	EPDC3	Electrical - Direct Connection Three Phase	2	Refer Specifications
40403	1	16010	EPDCN1	Electrical - Direct Connection Single Phase	48	Refer Specifications
40406	1	16010	EPDSW	Electrical - Disconnect Switch	16	Refer Specifications
40414	1	16010	EPJB	Electrical - Junction Box; Wall Mounted	80	Refer Specifications
40413	1	16010	EPJBC	Electrical - Junction Box; Circle - Ceiling Mounted	111	Refer Specifications
41869	1	16010	EPJBCUPS	Electrical - Junction Box; Circle - Ceiling Mounted - UPS	4	Refer Specifications
41724	1	16010	EPMMDS	Electrical - Mechanical Connection - Motor C/W Disconnect Switch	81	Refer Specifications
40422	1	16010	EPMTR	Electrical - Motor	15	Refer Specifications

ID	Grp	Div.	Code	Description	No	Notes
40426	1	16010	EPO110	Electrical - 10A 240V Single Power Outlt - Non Essential	2	Refer Specifications
40430	1	16010	EPO2	Electrical - Duplex Outlet	375	Refer Specifications
40432	1	16010	EPO2CL	Electrical - Duplex Receptacle - Ceiling Mounted	14	Refer Specifications
40433	1	16010	EPO2F	Electrical - Duplex Receptacle - Floor	3	Refer Specifications
40434	1	16010	EPO2S	Electrical - Double Receptacle Split Circuit	4	Refer Specifications
41718	1	16010	EPO2SP	Electrical - Duplex Outlet - Surge Protection Receptacle	100	Refer Specifications
41871	1	16010	EPO2SPUPS	Electrical - Duplex Outlet - Surge Protection Receptacle - UPS	1	Refer Specifications
41719	1	16010	EPO2T-S	Electrical - Duplex Receptacle - 5-20RA; T-Slot-Wall Mounted	130	Refer Specifications
41870	1	16010	EPO2UPS	Electrical - Duplex Outlet - UPS	34	Refer Specifications
40435	1	16010	EPO4	Electrical - 2 Duplex Receptacles - Wall	229	Refer Specifications
41721	1	16010	EPO4F	Electrical - 4-Plex Receptacle - Floor Mounted	12	Refer Specifications
40451	1	16010	EPPNLD	Electrical - Paneboard (U.N.O.) - Double Tub	7	Refer Specifications
40452	1	16010	EPPNLS	Electrical - Panelboard (U.N.O.) - Single Tub	15	Refer Specifications
41825	1	16010	EPPRP	Electrical - Panelboard - Relay Panel - Single Tub	1	Refer Specifications
40455	1	16010	EPRD	Electrical - Ceiling Mounted Products of Combustion Detector	85	Refer Specifications
40494	1	16010	FRFS	Fire - Sprinkler Flow Switch	5	Refer Specifications
40498	1	16010	FRHORN	Fire - Horn (Emergency Voice Communication) - Wall Mounted	3	Refer Specifications
41738	1	16010	FRHORNS	Fire - Horn (Emergency Voice Communication) - Wall Mounted with Strobe	21	Refer Specifications
40506	1	16010	FRPS	Fire - Sprinkler Low Pressure Switch	1	Refer Specifications
40527	1	16010	FRTS	Fire - Sprinkler Tamper Switch	3	Refer Specification
41378	1	16015	COMSPK	Comm - Public Address Speaker - Ceiling Mounted	224	Refer Specifications
40503	1	16015	FRMCP	Fire - Manual Call Point	21	Refer Specifications
40504	1	16015	FRMDH	Fire - Magnetic Door Holder	2	Refer Specifications
41874	1	16015	FRMDHUPS	Fire - Magnetic Door Holder - UPS	12	Refer Specifications
40507	1	16015	FRSAP	Fire - LCD Sub Annunciator Panel	3	Refer Specifications
40524	1	16015	FRSPKC	Fire - Emergency Evacuation Speaker (Ceil) - Recessed	124	Refer Specifications
41755	1	16020	SECMSCOF	Security - Ceiling Mounted Security Camera Outlet with Fixed Lens	11	Refer Specifications
41753	1	16020	SEDL	Security - Door Lock	45	Refer Specifications
41752	1	16020	SEDPS	Security - Magnetic Door Position Switch	91	Refer Specifications
41756	1	16020	SEPBBP	Security - Pushbutton with Pushplate	9	Refer Specifications
41116	1	16020	SEPCR	Security - Proximity Card Reader	78	Kantech is the current NH vendor of choice
41122	1	16020	SERTE	Security - Request To Exit Button	47	Refer Specifications
41123	1	16020	SESTK	Security - Electric Strike Lock	29	Refer Specifications
41754	1	16020	SEWMSCOF	Security - Wall Mounted Security Camera Outlet with Fixed Lens	17	Refer Specifications
41127	1	16020	SKP	Security - Key Pad	46	Refer Specifications

ID	Grp	Div.	Code	Description	No	Notes
40238	1	16025	EL2VBHR	Lighting - X-Ray Viewing 2 Bays High Recessed	4	Clinical Charts - 2 Panel Recess Mount 14x36 Spine Techline X-Ray View Box Illuminated
40280	1	16025	ELEBU	Lighting - Emergency Battery Unit - Wall	5	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40281	1	16025	ELEBURH	Lighting - Emergency Battery Unit & Remote Head	4	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40302	1	16025	ELHW	Lighting - Nom 1200mm 'Wing' Profile Surface Headwall Patient Light. w/- Room (Upward) & Reading (Downward) lighting. Switched at door; Headwall and Pillow speaker.	18	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40311	1	16025	ELMSEN	Lighting - Motion Sensor	66	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40312	1	16025	ELNL	Lighting - Night Light - Wall	35	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40379	1	16025	ELPOL	Lighting - Ceiling Mount Patient Observation Light - Dimmable from Door. (HC)	20	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
41759	1	16025	ELUCSL	Lighting - Under Cupboard MTD Strip Luminaire	5	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40370	1	16025	ELXCN1	Lighting - Ceiling Procedure Light	3	Trumpf TruLight 3000 - Ceiling Mounted
41740	1	16025	ELXSFDW	Lighting - Exit Light (Wall Mounted) - Single Face (Filled Quadrant Indicates Illuminated Faces)	8	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
40386	1	16025	ELXWH	Lighting - Examination Light Planet Wall Mounted - LED	7	Whelsh Allen Green Series 300 General Exam Lights. Wall Mounted.
41403	1	16029	ELXDDFE	Lighting - Exit Light (Ceiling) - Dual Face - Lines Indicate Face Side (Existing)	16	Refer Specifications and Indicative Design Luminaire Schedule for minimum requirements
41786	1	20000	AMPS	Amplifier for speakers	1	Northern Health Standard at Time of order
41788	1	20000	CMP	Telehealth - Ceiling Microphone	2	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)

ID	Grp	Div.	Code	Description	No	Notes
41785	1	20000	CSPK	Telehealth - Ceiling Speaker	4	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41787	1	20000	DMPSWCP	Telehealth - Digital Media Presentation System Wall Control Plate	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41804	1	20000	ELMC	Telehealth - Elmo camera	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41784	1	20000	FLRBX	Telehealth - Floorbox	8	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41811	1	20000	N48PSS	Network - 48 port POE Switch w/- stacking	18	Switch specifications are outlined in Schedule 1 Statement of Requirements Section 7.9.3
41809	1	20000	NCAB	Network - Cabling	1	Structured cabling specifications are outlined in Schedule 1 Statement of Requirements Section 7.9.4
41810	1	20000	NCABM	Network - Cabling Management	1	Cabling management specifications are outlined in Schedule 1 Statement of Requirements section 7.9.4.
41813	1	20000	NCORS	Network - Core Switch	1	Core switch specifications are outlined in Schedule 1 Statement of Requirements section 7.9.3 and will be further specified by Northern Health (NH) at the time of procurement.
41814	1	20000	NNMSFP	Network - Network Module w/- SFP	7	Small form-factor pluggable transceiver modules as required to connect network fibre to complete network connections based on the proponent's design.
41808	1	20000	NRACK	Network - Rack	6	General rack specifications are outlined in Schedule 1 Statement of Requirements section 7.9.3 and will be further specified by Northern Health at the time of procurement
41812	1	20000	NROUT	Network - Router	1	Refer to Northern Health's Reference Network Design. Additional Northern Health specifications will be provided at the time of procurement.

ID	Grp	Div.	Code	Description	No	Notes
41807	1	20000	NRWA	Network - Rooftop Wireless Antennae	1	As required for the wireless network based on vendor system requirements and NH specifications at the time of procurement.
41795	1	20000	PCFBTB	Telehealth - Patch cables - floor box to table box connections	2	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41783	1	20000	RACK	Telehealth - Rack	1	General rack specifications are outlined in Schedule 1 Statement of Requirements section 7.9.3 and will be further specified by NH at the time of procurement
41805	1	20000	SVVGAC	Telehealth - S-Video to VGA convertor	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41802	1	20000	TATM	Misc - TAT Monitor	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41789	1	20000	TBPD	Telehealth - Tablebox - power / data	8	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41790	1	20000	TBPDHDMI	Telehealth - Tablebox - power / data / VGA 3.5 / HDMI	4	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013)
41778	1	20000	TEL	Telecom - Telephone; Desk Top Phone	68	Refer to response to RFI 023. NH will provide additional specifications at the time of procurement.
41779	1	20000	TELC	Telecom - Telephone; Conference	1	Refer to Schedule 1 Statement of Requirements section 7.9.7 and response to RFI 023.
41777	1	20000	TELP	Telecom - Telephone; Public Pay Phone	2	Refer to Schedule 1 Statement of Requirements section 7.9.7 and response to RFI 023. NH will provide additional specifications at the time of procurement and after review of the detailed design.
41796	1	20000	TELPC	Telecom - Telephone; Polycomm Conference Phone	3	Refer to Schedule 1 Statement of Requirements section 7.9.7 and response to RFI 023. NH will provide additional specifications at the time of procurement and after review of the detailed design.

ID	Grp	Div.	Code	Description	No	Notes
41815	1	20000	TELPS	Telephone - Phone System	1	Refer to Schedule 1 Statement of Requirements section 7.9.7 and response to RFI 023.
41865	1	20000	TELW	Telecom - Telephone (wall mount)	16	Refer to Schedule 1 Statement of Requirements section 7.9.7 and response to RFI 023. NH will provide additional specifications at the time of procurement and after review of the detailed design.
41864	1	20000	TELWR	Telecom - Telephone (wall mount; recess into partition)	1	Refer to Schedule 1 Statement of Requirements section 7.9.7 and response to RFI 023. NH will provide additional specifications at the time of procurement and after review of the detailed design.
41797	1	20000	TVM	Telehealth - Television Monitor - LED / HD	3	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41801	1	20000	TVM55	Telehealth - Television - 55 LED / HD Monitor	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41781	1	20000	TVM65	Telehealth - Television - 65 LED / HD Monitor	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41782	1	20000	TVMT	Telehealth - Television Wall Mount - Tilting	5	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41817	1	20000	V8BBC	Vocera - 8 Bay Battery Chargers for Vocera Badge Batteries	10	Refer to Schedule 1 Statement of Requirements section 7.9.6 and as specified by the NH to support Vocera Badges at the time of procurement.
41816	1	20000	VBB	Vocera - Batteries for Badges	150	Refer to Schedule 1 Statement of Requirements section 7.9.6 and as specified by the NH to support Vocera Badges at the time of procurement.
41794	1	20000	VCUCC	Telehealth - VCU Camera Cable	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41780	1	20000	VCUCP	Telehealth - VCU Codec Package	3	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).

ID	Grp	Div.	Code	Description	No	Notes
41791	1	20000	VCUCS	Telehealth - VCU - Camera Shelf	3	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41799	1	20000	VCUCWM	Telehealth - VCU Codec wall mount with cable cover	2	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41803	1	20000	VCUD	Telehealth - VCU Desktop	1	Refer to Northern Health Audio Visual Technical Guidelines & Specifications (April 15, 2013).
41793	1	20000	VCUW	Telehealth - VCU 1 year mandatory warranty	4	All VCU equipment should have a minimum warranty of 1 year.
41821	1	20000	VEW	Vocera - Vocera Extended Warranty	1	An extended warranty of two years is required in addition to the standard 1 year Vocera warranty.
41823	1	20000	VNICPC	Vocera Nursecall Integration - Connexall PC to run SIC	1	As specified by the vendor and NH at the time of procurement to complete the install of the Vocera Nursecall integration
41824	1	20000	VNISCB	Vocera Nursecall Integration - Precidia or Lantronics serial to IP converter box & License	1	As specified by the vendor and NH at the time of procurement to complete the install of the Vocera Nursecall integration
41822	1	20000	VTITS	Vocera Telephony - Telephony SIP Server	1	As required for Vocera System integration and as specified by NH at the time of procurement
41818	1	20000	VUC	Vocera - Universal Clips 10 - Bx/25)	10	As specified by the vendor and NH at the time of procurement to complete the install of the Vocera system
41819	1	20000	VUL	Vocera - Universal Lanyards 10 - Bx/25)	10	As specified by the vendor and NH at the time of procurement to complete the install of the Vocera system
41820	1	20000	VVB	Vocera - Vocera badges (quantaty 75)	75	Refer to Schedule 1 Statement of Requirements section 7.9.6 and as specified by the vendor and NH at the time of procurement to support all required functions with the latest technology
41800	1	20000	WAP	Network - Wireless Access Point	42	As required for the wireless network based on vendor system requirements and Schedule 1 Statement of Requirements section 7.9.5.

ID	Grp	Div.	Code	Description	No	Notes
40008	1	30001	BC3	Bookcase - Full Height Open Bookcase	3	Northern Health Standard at Time of order
40056	1	30001	CHC	Chair - Conference	51	Northern Health Standard at Time of order
40057	1	30001	CHD	Chair - Dining	44	Northern Health Standard at Time of order
41594	1	30001	CHDECK	Chair - Patient & Visitor Outdoor Deck Chair	12	Northern Health Standard at Time of order
40060	1	30001	CHES	Chair - Examination Stool	7	Northern Health Standard at Time of order
40061	1	30001	CHFS	Chair - Folding Stackable Chair	20	Northern Health Standard at Time of order
40063	1	30001	CHKC	Chair - Kindergarden Chair	4	Northern Health Standard at Time of order
40064	1	30001	CHL1S	Chair - Lounge Single Seater	12	Northern Health Standard at Time of order
40065	1	30001	CHL2S	Chair - Lounge Two Seater	2	Northern Health Standard at Time of order
40069	1	30001	CHPAC	Chair - Patient Chair	16	Northern Health Standard at Time of order
40073	1	30001	CHSC	Chair - Staff Clerical	64	Northern Health Standard at Time of order
40076	1	30001	CHTUB	Chair - Tub Chair 620 wide	1	Northern Health Standard at Time of order
40077	1	30001	CHV	Chair - Visitor	90	Northern Health Standard at Time of order
40082	1	30001	CHWS	Chair - Waiting Single Seat	39	Northern Health Standard at Time of order
41609	1	30001	DACDRYL	Domestic Appliance - Commercial Dryer; Large.	1	Unimac - refer to cut sheet in Data Room
41608	1	30001	DACDRYS	Domestic Appliance - Commercial Dryer; Small.	1	Unimac - refer to cut sheet in Data Room
41606	1	30001	DACLWM	Domestic Appliance - Commercial Washing Machine	2	Unimac
40191	1	30001	DADRY	Domestic Appliance - Domestic Clothes Dryer	1	Unimac
40188	1	30001	DAMW	Domestic Appliance - Microwave Oven	6	Sears, Kenmore or Equal
40189	1	30001	DAOH	Domestic Appliance - Oven & Hotplates	2	Sears, Kenmore or Equal
40192	1	30001	DAWM	Domestic Appliance - Clothes Washing Machine	2	Sears, Kenmore or Equal
40481	1	30001	FC4	Filing cabinet - 4 drawer	30	Northern Health Standard at Time of order
41741	1	30001	FXPTS	Fixture - Public Pay Telephone and Stand	1	Northern Health Standard at Time of order
40650	1	30001	LK2	Locker - Two Half Height Lockers	21	Northern Health Standard at Time of order
40711	1	30001	MDSPYD	Medical Diagnostic Equipment - Diagnostic Set Wall Mounted	14	Welsh Allen Green Series 777 Integrated Wall System.
41682	1	30001	MQBS4	Medical Equipment - Refrigerated Body Storage Unit - 4 Bodies.	1	Refer Quote from Somagen Diagnostics, Dec 6, 2012. (In Cut Sheets)

ID	Grp	Div.	Code	Description	No	Notes
41600	1	30001	MQERPL	Medical Equipment - Emergency Room Pendant & Surgical Light	2	Olympus TruPort Surgical Pendant with Trumpf TruLight 1000 Universal Light. Refer Cut sheet for accessories and configuration.
41052	1	30001	REF1	Refrigerator - Under Counter Beverage	2	Sears, Kenmore or Equal
41628	1	30001	REF11	Refrigerator - Upright Freezer 18.2cf	3	Sears, Kenmore or Equal
41070	1	30001	REF3	Refrigerator - Upright Domestic; Freezer Over 15cf	1	Sears, Kenmore or Equal
41076	1	30001	REF7	Refrigerator - Upright Domestic Top Freezer 27.1cf	6	Sears, Kenmore or Equal
41598	1	30001	REFBAR	Refrigerator - Built-Int Bar Fridge	1	Sears, Kenmore or Equal
41133	1	30001	STOW2	Storage Unit - Metal Shelving Unit 300d	17	Northern Health Standard at Time of order
41134	1	30001	STOW3	Storage Unit - Metal Shelving Unit 450d	40	Northern Health Standard at Time of order
41135	1	30001	STOW4	Storage Unit - Metal Shelving Unit 600d	98	Northern Health Standard at Time of order
41170	1	30001	TVCEIL	Television - Ceiling Mounted TV Set	10	Northern Health Standard at Time of order
41176	1	30001	TVFSD	Television - DVD c/w Stand	1	Northern Health Standard at Time of order
41183	1	30001	TVWALL	Television - 32 Flat Panel Wall Mounted	17	Northern Health Standard at Time of order
41387	1	30001	WTBR	Window Treatment - Roller Blind	73	Refer Indicative Design Specifications for minimum requirements
41707	1	30001	WTFC	Window Treatment - Fabric Curtain/s and Track	17	Northern Health Standard at Time of order
41497	2	10800	FXBMA	Fixture - Monitor Arm Bracket - Wall Mounted	14	Northern Health Standard at Time of order
40535	2	10800	FXBMW	Fixture - Monitor Bracket Wall Channel	15	Amico CPU Mount 3
41459	2	10800	FXLAR	Fixture - X-Ray Lead Apron Rack	1	Northern Health Standard at Time of order
41137	2	10800	STOWDSL	Storage Unit - Dangerous Drug Wall Safe - Large	1	Medicus Health - Medium Narcotics Box - Lockable 16"x12"x9". http://www.medicus-health.com/narcotics-boxes-lockable-medium.aspx
40246	2	16025	ELBIRTH	Lighting - Birthing Light	1	KLM Medical Equipment LLC. Argos II Birthing Room Lights http://www.klmmedicalequipment.com/skytron/skytron-products/lights/birthing-room-lights
41640	2	16025	ELMLW	Lighting - SPU Magnifying Lens; Wall Mounted.	1	Daylight Ultra Slim Magnifying Lamp XR, White - Wall Mounted LED Fitting. http://ca.daylightcompany.com/product/ultra-slim-magnifying-lamp-xr/

ID	Grp	Div.	Code	Description	No	Notes
40019	2	30001	BINCW240L	Bin - Contaminated Waste Wheeled 240 Litre	2	Northern Health Standard at Time of order
41596	2	30001	BINCWL	Bin - Contaminated Waste Large	5	Northern Health Standard at Time of order
41597	2	30001	BINCWS	Bin - Contaminated Waste Small	50	Northern Health Standard at Time of order
40020	2	30001	BINDKW	Bin - Domestic Kitchen Waste	5	Northern Health Standard at Time of order
41576	2	30001	BINMED	Bin - Medications Room Waste Bin	1	Northern Health Standard at Time of order
40021	2	30001	BINNC240L	Bin - Non Contaminated Waste Wheeled 240 Litre	1	Northern Health Standard at Time of order
40022	2	30001	BINRW240L	Bin - Recycle Waste Wheeled 240 Litre	1	Northern Health Standard at Time of order
40025	2	30001	BINSN	Bin - Sanitary Napkin	14	Northern Health Standard at Time of order
40026	2	30001	BINWPL	Bin - Office Waste Paper Large	1	Northern Health Standard at Time of order
40027	2	30001	BINWPS	Bin - Office Waste Paper Small	41	Northern Health Standard at Time of order
40031	2	30001	BSLD	Bedside Locker Mobile w/ Drawers 450w	17	Northern Health Standard at Time of order
41510	2	30001	CHBWS	Chair - Bariatricity Waiting Single	1	Northern Health Standard at Time of order
41592	2	30001	CHHD	Chair - Client Hairdressing.	1	Northern Health Standard at Time of order
40070	2	30001	CHPHC	Chair - Phlebotomy Chair	2	Northern Health Standard at Time of order
40071	2	30001	CHPR	Chair - Patient Recliner	2	Northern Health Standard at Time of order
41585	2	30001	DESK7	Desk - Consulting Room Desk 1200 x 750	9	Northern Health Standard at Time of order
41529	2	30001	LABSC2B.13	Biological Safety Cabinet Class II. Type 2B - 1362mm	2	BioChemGARD Class II, Type B2 Biosafety Cabinet. http://www.bakerco.com/images/stories/pdf/brochures/biochemgard-brochure-web.pdf
41637	2	30001	MCSFSF	Medical Cleaning Equipment - Small Flash Sterilizer; Freestanding	1	Steris Amsco Century Small Sterilizer - Domestic
41638	2	30001	MCUWSU	Medical Cleaning Equipment - Steris Utensil Washer Sanitizer Under Counter	1	Miele Washer Sanitizer
41496	2	30001	MDMONP	Medical Diagnostic Equipment - Patient Bedside Physiological Monitor (MP50)	14	Philips - MP50 Patient Monitor.
41495	2	30001	MDMONS	Medical Diagnostic Equipment - Patient Monitoring Database Server (M3154)	1	Philips - IntelliVue M3154 Database Server.
40713	2	30001	MDSPYW	Medical Diagnostic Equipment - Sphygmomanometer Wall Mounted	25	Welch Allyn - Sphygmomanometers - 767 Wall and Mobile Aneroids http://www.welchallyn.com/apps/products/product.jsp?id=19-br-96-1266504768631
40695	2	30001	MQWC	Medical Cleaning Equipment - Warming Cabinet	1	Steris - Amsco Warming Cabinet

ID	Grp	Div.	Code	Description	No	Notes
40940	2	30001	PHYBAR	Physiotherapy - Parallel Walking Bars	1	Edutek- Parallel Walking Bars 9234. http://www.eduteklabs.com/parallel-walking-bar-234.html
41652	2	30001	PHYWWP	Physiotherapy - Wall Mounted Pulley Weights.	1	RehabMart Hausmann Industries Duplex Pulley Weights http://www.rehabmart.com/product/duplex-pulley-weights-12637.html
41068	2	30001	REF2	Refrigerator - Underbench Drug Storage Lockable	2	Living Direct - ABTUCFS0204G-ft. Freestanding White
41136	2	30001	STOWC	Storage Unit - Compactus Mobile Storage	1	Northern Health Standard at Time of order
41662	2	30001	STOWFLC	Storage Unit - Flamable Liquid Storage Cabinet. 36w x 35h x 24d.	1	Northern Health Standard at Time of order
41148	2	30001	TABR	Table - Boardroom 1800 x 900	1	Northern Health Standard at Time of order
41149	2	30001	TACPT	Table - Childrens Play Table	1	Northern Health Standard at Time of order
41151	2	30001	TACTM	Table - Coffee Table Medium	4	Northern Health Standard at Time of order
41152	2	30001	TACTS	Table - Coffee Table Small	1	Northern Health Standard at Time of order
41153	2	30001	TAD4S	Table - Dining Table 4 Seater. 1350 x 700	9	Northern Health Standard at Time of order
41595	2	30001	TADECK	Table - Patient & Visitor Deck Table1800 x 900	3	Northern Health Standard at Time of order
41159	2	30001	TAR15X9	Table - Rectangular 1500 x 900	6	Northern Health Standard at Time of order
41645	2	30001	WGTRK	Weight Rack - 2 Shelves for dumbbells	2	Northern Health Standard at Time of order
41247	2	30001	WS2	Workstation - Corner Desk 1800 x 1800 Complete with Pedestall	26	Northern Health Standard at Time of order
40084	3	20000	CLERATM	Clerical - Automatic Teller Machine	1	Supplied and installed by Northern Health
40085	3	20000	CLERBAR	Clerical - Bar Code Reader	7	Supplied and installed by Northern Health
41546	3	20000	CLERLAP	Clerical - Label Printer	17	Supplied and installed by Northern Health
40090	3	20000	CLERPC	Clerical - Personal Computer Terminal	60	Supplied and installed by Northern Health
41665	3	20000	CLERPCW	Clerical - Computer - Wall Mounted (SSM IT Station)	16	Supplied and installed by Northern Health
40092	3	20000	CLERPM	Clerical - Photocopier Medium	13	Supplied and installed by Northern Health
40094	3	20000	CLERPRN	Clerical - Printer; Network	7	Supplied and installed by Northern Health
41775	3	20000	CLERTC	Clerical - Thin Client	7	Supplied and installed by Northern Health
41776	3	20000	CLERTCW	Clerical - Thin Client - Wall Mounted	4	Supplied and installed by Northern Health
41142	3	20000	MQPMS1	Medical Equipment - Pixus Drug Dispensing Machine - Single	1	Supplied and installed by Northern Health

ID	Grp	Div.	Code	Description	No	Notes
40012	3	30001	BEDBAS	Bed - Infant Bassinet	1	Supplied and installed by Northern Health
40013	3	30001	BEDCC	Bed - Consulting Couch	7	Supplied and installed by Northern Health
40014	3	30001	BEDDOM	Bed - Standard Single Domestic Bed	1	Supplied and installed by Northern Health
41826	3	30001	BEDFPT	Bed - Freestanding Procedures Table	1	Amsco 3085 SP - Surgical Table - supplied and installed by Northern Health
40018	3	30001	BEDPS	Bed - Secure Psych Bed	1	Supplied and installed by Northern Health
40017	3	30001	BEDSP	Bed - Standard In-Patient Bed	9	Supplied and installed by Northern Health
41601	3	30001	BEDTER	Bed - Trauma Emergency Room	1	Supplied and installed by Northern Health
40034	3	30001	CACL92	Cart - Clean Linen Impress Cart - 920 Long	9	Supplied and installed by Northern Health
40035	3	30001	CACLNR	Cart - Cleaners Cart	5	Supplied and installed by Northern Health
40037	3	30001	CADLS	Cart - Dirty Linen Skip	3	Textile Innovations - Single Medium Duty Steel Hamper No. 696 Model RB696. http://textileinnovations.com/single-medium-duty-steel-hamper-692-p-61.html - supplied and installed by Northern Health.
40041	3	30001	CAMC	Cart - Medication Cart	1	Lion Ville - 800 Series 12 Patient Drawer - supplied and installed by Northern Health.
41863	3	30001	CAMS	Cart - Consulting Room Medical Supplies.	6	Waterloo Healthcare Medical Cart. Model UTRLU-433369- Colour to be selected - supplied and installed by Northern Health.
41641	3	30001	CAPH3	Cart -Pharmacy Storage Wire Shelving 920 long.	6	Supplied and installed by Northern Health
41642	3	30001	CAPH4	Cart -Pharmacy Storage Wire Shelving 1220 long.	3	Supplied and installed by Northern Health
41643	3	30001	CAPH5	Cart -Pharmacy Storage Wire Shelving 1530 long.	1	Supplied and installed by Northern Health
41678	3	30001	CAPH6	Cart -Pharmacy Storage Solid Shelving 1530 long.	1	Supplied and installed by Northern Health
41666	3	30001	CASPC	Cart - Sterile Processing Cart.	2	Supplied and installed by Northern Health
40078	3	30001	CHW	Chair - Wheel Chair	2	Supplied and installed by Northern Health
40086	3	30001	CLERCR	Clerical - Cash Register	1	Supplied and installed by Northern Health
40097	3	30001	CLERSHR	Clerical - Shredder	3	Supplied and installed by Northern Health
40144	3	30001	CTNBED	Curtain - Bedscreen Curtain	36	Supplied and installed by Northern Health

ID	Grp	Div.	Code	Description	No	Notes
40145	3	30001	CTNSHR	Curtain - Shower Screen Curtain	18	Supplied and installed by Northern Health
40183	3	30001	DESK2	Desk - Large 1800 x 900	3	Supplied and installed by Northern Health
41702	3	30001	DISWHC	Dispenser - Waterless Hand Cleaner	69	Supplied and installed by Northern Health
40646	3	30001	LABMS	Laboratory - Microscope	1	Supplied and installed by Northern Health
41855	3	30001	LABWF	Laboratory Equipment - Water Filter for Cobas.	1	Supplied and installed by Northern Health
41639	3	30001	MCDCR	Medical Cleaning Equipment - SPU Drying / Cooling Rack	1	Supplied and installed by Northern Health
41774	3	30001	MCUC	Medical Cleaning Equipment - Ultrasonic Cleaner - Counter Top	1	Emerson Bransonic Cleaner Model 1510 - supplied and installed by Northern Health.
41828	3	30001	MDFM	Medical Diagnostic Equipment - Foetal Monitor FM50	1	Philips Avalon FM 50, M2720A and M2703A - supplied and installed by Northern Health.
40704	3	30001	MDMONC	Medical Diagnostic Equipment - Central; Patient Physiological Monitor (M3155)	3	Philips - IntelliVue M3155 Information Center - supplied and installed by Northern Health.
41806	3	30001	MDMONI	Medical Diagnostic Equipment - Central Physiological Information Center Monitor (M3151)	1	Philips IntelliVue M3151 Information Center Client - supplied and installed by Northern Health.
41847	3	30001	MGBIP	Medical Equipment - Baxter Infusion Pump	16	Supplied and installed by Northern Health
41829	3	30001	MQBBU	Medical Equipment Blendox 960 Blendox N2O Inhalation Analgesia Unit - Blender	1	Supplied and installed by Northern Health
41851	3	30001	MQBCM	Medical Equipment - Breath Carbon Monoxide Monitor	1	Supplied and installed by Northern Health
41835	3	30001	MQBP	Medical Equipment - Breast Pump	1	Supplied and installed by Northern Health
41450	3	30001	MQC	Medical Equipment Centrifuge	1	Helmer Scientific - supplied and installed by Northern Health.
41830	3	30001	MQCR	Medical Equipment - Cardiac Reader	1	Cobas - Roche Cardiac Reader - supplied and installed by Northern Health.
41840	3	30001	MQDEF	Medical Equipment - Defibrillator	1	Supplied and installed by Northern Health
41832	3	30001	MQDIG	Medical Equipment - Digitizer	1	CR 30 - X Digitizer - supplied and installed by Northern Health.
41837	3	30001	MQFHD	Medical Equipment - Foetal Heart Detector	1	Supplied and installed by Northern Health
41834	3	30001	MQGPU	Medical Equipment - Giraffe - Phototherapy Unit	1	Supplied and installed by Northern Health
41838	3	30001	MQISTAT	Medical Equipment - I-Stat Portable Clinical Analyzer	1	Supplied and installed by Northern Health
41859	3	30001	MQNSR	Medical Equipment - Nerve stimulator	1	Supplied and installed by Northern Health

ID	Grp	Div.	Code	Description	No	Notes
41845	3	30001	MQOCU	Medical Equipment - Oxygen Concentrator Unit	2	Supplied and installed by Northern Health
41860	3	30001	MQPUM	Medical Equipment - Phototherapy Units and Meter	1	Supplied and installed by Northern Health
40773	3	30001	MQRES	Medical Equipment - Resuscitation Cart	1	Supplied and installed by Northern Health
40777	3	30001	MQRIP	Medical Equipment - Rapd Infusion Pump	1	Supplied and installed by Northern Health
41839	3	30001	MQSPR	Medical Equipment - Spirometer	1	Supplied and installed by Northern Health
41833	3	30001	MQVSM	Medical Equipment - Vital Signs Monitor	1	Welch Allyn Connex Vital Signs Monitor 6000 Series - supplied and installed by Northern Health.
40943	3	30001	PHYCOUCHM	Physiotherapy - Plinth Treatment Couch Medium	2	Supplied and installed by Northern Health
41615	3	30001	PHYPLINTH	Physiotherapy - Plinth	1	Supplied and installed by Northern Health
40944	3	30001	PHYTREADL	Physiotherapy - Treadmill Large	1	Supplied and installed by Northern Health
41629	3	30001	REF107	Refrigerator - Lockable Upright Drug Refrigerator	1	Supplied and installed by Northern Health
41701	3	30001	STOWPBSU	Storage Unit - Mobile Patient Bathroom Storage Unit	8	Sterilite 4-Drawer lightweight plastic Cart on Casters - White - supplied and installed by Northern Health.
41676	3	30001	STOWSPG	Storage Unit - Steel Pharmacy Condola 900 x 300 x 1800	31	Supplied and installed by Northern Health
41146	3	30001	STRCHPT	Stretcher - Patient Transport	1	Supplied and installed by Northern Health
41157	3	30001	TAOBT	Table - Patient Over Bed Table	9	Supplied and installed by Northern Health
41179	3	30001	TV32LCD	Television - 32 Flat Panel LCD TV Wall Mounted	1	Supplied and installed by Northern Health
41440	3	60001	MDMONPACS	Medical Diagnostic Equipment - PACS Monitor	3	Supplied and installed by Northern Health
41854	3	60001	MQCSM	Medical Equipment - CS Monitor	1	Supplied and installed by Northern Health
41518	3	60001	RADTGXC	Radiology Equipment - General X-Ray System Control Console	1	Supplied and installed by Northern Health
41520	3	60001	RADTGXGEN	Radiology Equipment - General X-Ray Generator Control Cabinet	1	Supplied and installed by Northern Health
41029	3	60001	RADTGXGTY	Radiology Equipment - General Overhead X-Ray Tube and Gantry	1	Supplied and installed by Northern Health
41521	3	60001	RADTGXSIU	Radiology Equipment - General X-Ray System Interface Unit	1	Supplied and installed by Northern Health
41515	3	60001	RADTGXT	Radiology Equipment - General X-Ray Table	1	Supplied and installed by Northern Health
41519	3	60001	RADTGXUPS	Radiology Equipment - General X-Ray System UPS	1	Supplied and installed by Northern Health
41517	3	60001	RADTGXVB	Radiology Equipment - General X-Ray Virticle Buckey	1	Supplied and installed by Northern Health

ID	Grp	Div.	Code	Description	No	Notes
41049	3	60001	RADXM	Radiology Equipment - X-Ray - Mobile	1	Includes all X-Ray Equipment - supplied and installed by Northern Health.
41727	4	30001	4BEDBAS	Bed - Infant Bassinet - Relocated	1	Supplied and installed by Northern Health
41728	4	30001	4BEDCC	Bed - Consulting Couch - Relocated	4	Supplied and installed by Northern Health
41580	4	30001	4BEDDEL	Bed - Single Delivery Bed - Relocated	1	Supplied and installed by Northern Health
41700	4	30001	4BEDLTC	Bed - Standard Long Term Care Bed - Relocated	9	Supplied and installed by Northern Health
41729	4	30001	4BEDTER	Bed - Trauma Emergency Room - Relocated	1	Supplied and installed by Northern Health
41669	4	30001	4LABCDYN	Lab Equipment - Cell Dyne - Preliminary - Relocated	1	Supplied and installed by Northern Health
41661	4	30001	4LABCOBAS	Laboratory - Cobas C 311 - Relocated	1	Supplied and installed by Northern Health
41730	4	30001	4LABMS	Laboratory - Microscope - Relocated	1	Supplied and installed by Northern Health
41668	4	30001	4LABRTFX32	Lab Equipment - Rotofx32 - Preliminary - Relocated	1	Supplied and installed by Northern Health
41670	4	30001	4LABSTL	Lab Equipment - Stalo - Preliminary - Relocated	1	Supplied and installed by Northern Health
40698	4	30001	4MDECG	Medical Diagnostic Equipment - ECG Machine; Relocated.	1	Supplied and installed by Northern Health
41858	4	30001	4MQABP	Medical Equipment - Autotransfusion Unit Blood Processing; Relocated.	1	Supplied and installed by Northern Health
41663	4	30001	4MQBH	Medical Equipment - Bair Hugger Temperature Management Unit - Relocated	1	Supplied and installed by Northern Health
41846	4	30001	4MQC	Medical Equipment Centrifuge - Relocated	4	Supplied and installed by Northern Health
41852	4	30001	4MQCCR	Medical Equipment - CR Reader - Relocated	1	Supplied and installed by Northern Health
41848	4	30001	4MQCRS	Medical Equipment - Cast Removal Saw; Relocated.	1	Supplied and installed by Northern Health
41841	4	30001	4MQDEF	Medical Equipment - Defibrillator LP20 - Relocated	2	Supplied and installed by Northern Health
41844	4	30001	4MQEFP	Medical Equipment - Eteral Feeding Pump; Relocated.	2	Supplied and installed by Northern Health
41651	4	30001	4MQHYDROC	Medical Equipment - Hydroculator - Relocated	1	Supplied and installed by Northern Health
41726	4	30001	4MQRES	Medical Equipment - Resuscitation Cart - Relocated	1	Supplied and installed by Northern Health
41614	4	30001	4MQRESTAIR	Medical Equipment - Infant Resuscitation Crib - Relocated	1	Supplied and installed by Northern Health
41842	4	30001	4MQSTU	Medical Equipment - Suction Transport Unit- Relocated	4	Supplied and installed by Northern Health
41849	4	30001	4MQTHR	Medical Equipment -Thermometer; Relocated.	4	Supplied and installed by Northern Health
41850	4	30001	4MQTON	Medical Equipment - Applanation Tonometer; Relocated.	1	Supplied and installed by Northern Health
41857	4	30001	4MQVENT	Medical Equipment - Ventilator; Relocated	1	Supplied and installed by Northern Health

ID	Grp	Div.	Code	Description	No	Notes
41856	4	30001	4MQVF	Medical Equipment - Vein Finder; Relocated	1	Supplied and installed by Northern Health
41843	4	30001	4MQVTLR	Medical Equipment - Ventilator; Relocated	1	Supplied and installed by Northern Health
40941	4	30001	4PHYBIKE	Physiotherapy - Upright Exercise Bike - Relocated	1	Supplied and installed by Northern Health
41653	4	30001	4PHYPF	Physiotherapy - Pilates Frame - Relocated	1	Supplied and installed by Northern Health
41654	4	30001	4PHYSF	Physiotherapy - Ski Fitter - Relocated	1	Supplied and installed by Northern Health
41664	4	30001	4PHYUSM	Physiotherapy - Ultrasound Therapy Machine - Relocated	1	Supplied and installed by Northern Health
41060	4	30001	4REF12	Refrigerator - Laboratory Refrigerator; Large Upright Double Door - Relocated	1	Supplied and installed by Northern Health
41660	4	30001	4REF16	Refrigerator - Laboratory Blood Refrigerator; Upright Single Door - Relocated	1	Supplied and installed by Northern Health
41084	4	30001	4SCBCS	Scale - Baby Countertop Scale - Relocated	1	Supplied and installed by Northern Health
41731	4	30001	4TAOBT	Table - Patient Over Bed Table - Relocated	12	Supplied and installed by Northern Health